



skala 1:20



Technical drawing of a square column cross-section. The drawing shows a square column with a side length of 25 cm. The reinforcement details are as follows:

- 1** 4Ø12: Four longitudinal bars at the top.
- 2** 4Ø12: Four longitudinal bars at the bottom.
- 3** Ø10: Stirrups (circles) for transverse reinforcement.
- 4** Ø6 co 10 i 15cm: Transverse bars (crosses) with a spacing of 10 cm horizontally and 15 cm vertically.
- 5** Ø10: Stirrups (circles) for transverse reinforcement.
- 6** Ø10: Stirrups (circles) for transverse reinforcement.
- C'**: A label pointing to the center of the column.



NR	A0	B500SP	DŁUG.	szt.	A0	B500SP
	Ø	Ø	cm		Ø6	Ø12
1		12	322	4		12,9
2		12	410	4		16,4
3		12	185	4		7,4
4	6		96	58	55,7	
DŁUGOŚĆ m					55,7	36,7
CIĘŻAR kg/m					0,222	0,888
CIĘŻAR kg					12,4	32,6

otulina 2,5 cm
BETON B30 (C25/30)
STAL A0 - Stos
B500SP

 Pro Amar PRACOWNIA PROJEKTOWA SP Z O.O. ul. Dworcowa 40/4 85 -010 Bydgoszcz tel./fax 052-345-66-87 NIP 554-10-20-146		NAZWA INWENSTYCJI: ZESPÓŁ BUDYNKÓW MIESZKALNYCH WIEŁORODZINNYCH Z CZĘŚCIĄ USŁUGOWO-HANDLOWĄ NA DZ. NR EW. 43/1, 43/2, 44/1, 44/2, 45, 46, 49, 50, 51 OBR. 113	
STADIUM: PROJEKT WYKONAWCZY		BRANŻA: KONSTRUKCJA	
ADRES INWENSTYCJI:		NR RYSUNKU	
BYDGOSZCZ ul. Zygmunta Augusta budynek A		131/k/271	
INWESTOR:		DATA	
Bydgoskie Towarzystwo Budownictwa Społecznego Sp. z o.o. ul. Grunwaldzka 64, 85-239 Bydgoszcz		12.09.2022r.	
NAZWA RYSUNKU:		SKALA	
P.7.2.1.SŁUP NA 6 i 5 PIĘTRZE W OSI 6C'		1:20	
PROJEKTANT:		PODPIS	
mgr inż. Jan Mądry nr upr. NB-W-7210/129/78 CZŁONEK K-PO IZBY INŻYNIERÓW BUD. KUP/BO/1568/01			
OPRACOWANIE:		PODPIS	
technik bud. Teresa Czekajewska			
SPRAWDZAJĄCY:		PODPIS	
mgr inż. Zbigniew Mądry upr. nr WKP/0023/POOK/03 CZŁONEK W.O. IZBY INŻ. BUD. WKP/BO/0424/04			